BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Dasarahalli Division

D.T.S

Repairing work Range office Building, removal of debries and providing new precast RCC covering slabs desilting of drains in ward no.13 Mallasandra

S No	Item Name	Unit	Quantity	Rate In Figure in Rs	
				In Figures	in words
1	Providing skilled labour (mazdoor Heavy)for removal of debris, slabs resetting,desilting of drains and other ward maintainence works. (Pg No -LVI, & Itm No 5)	Day	1080.00		
2	Hire charges of Tractor 40HP including cost of driver, Fuel and other incidental charges. (Pg No-XLVIII, Sl. No.19)	Day	90.00		
3	Hire charges of JCB excavator including cost of driver, Fuel and other incidental charges. (Pg No-XLVIII, Sl. No.23)	Day	120.00		
4	Removing and Re Setting of Footpath slabs (PWD SR 2018-19 P.No: 270, I.No.: 37.56)	Sqm	450.00		
5	Providing and laying 25cm thick Pre Cast Cover slabs including cost of all materials, labours, curing, transportation, loding unloding etc.., complete as per the direction of Engineer in charge.	Sqm	18.00		
6	Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge (Data Rate)	Sqm	110.16		
7	Providmg SS pipe name boards-made of 2" (65mm) dia SS pipe for vertical pole and 3no of horizontal support pipe of 11/2" dia. pipe each of length 1.00 mtr sinage board of size 60x45cm and 60x23cm size made of 16 guage SS sheet welded to SS tube frame of size 25x25 mm all manual are cut size and all items electricals welded as per the drawing all Joints are grainded smooth and pasted along with the sticker printed the name of the road and name of the elected mambers fixed to ground in 1 : 2 :4 with PCC at the bottom, all cost inclusive of lead a nd lifts Chapter, 530.0	No	58.00		

ಕಂಡಿಕೆ( )ರಲ್ಲಿ ವಿವರಿಸಿರುವ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು(.ದಾ:ಲಿ.....)ರವರು
ದೃಢೀಕರಿಸಿಕೊಳ್ಳುವ ಷರತ್ತಿಗ ಒಳಪಡಿಸಿ ಡಿ.ಟಿ.ಎಸ್
ಅನುಮೋದಿಸಿದೆ.
ಸದರಿ ಟೆಂಡರ್ ಷೆಡ್ಯೂಲ್‌ನ್ನು ತಿದ್ದುಪಡಿ ಮಾಡಿದಂತೆ
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.
ತಿದ್ದುಪಡಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ:.....Nill.....
ರದ್ದುಪಡಿಸಿರುವ ಒಟ್ಟು ವಿಭಾಗಗಳ ಸಂಖ್ಯೆ:...Nill...

Number of corrections

Executive Engineer
Dasarahalli Division

Page 1 of 1

DTS Approved

" DTS Approved "

ಮುಖ್ಯ ಅಭಿಯಂತರರು (ದಾಸರಹಳ್ಳಿ)